





- LEGEND - LAYOUT PLAN**
- SWALE DRAIN, PIT & PROPERTY INLET
  - SWALE DRAIN
  - SEWER & MAINTENANCE STRUCTURES
  - HOUSE DRAIN
  - SERVICE CONDUITS
  - TACTILE PAVERS
  - EXISTING ELECTRICITY (UNDERGROUND)
  - EXISTING ELECTRICITY (OVERHEAD)
  - EXISTING COMMUNICATIONS
  - EXISTING GAS
  - EXISTING TELSTRA
  - EXISTING WATER
  - EXISTING STORMWATER DRAIN
  - EXISTING SEWER
  - EXISTING HOUSE DRAIN
  - EXISTING SWALE DRAIN
  - EXISTING SURFACE LEVEL
  - FINISHED BUILDING LINE LEVEL
  - FINISHED RIDGE LINE LEVEL
  - TOP OF RETAINING WALL
  - BOTTOM OF RETAINING WALL
  - RETAINING WALL
  - ZERO LOT LINES
  - PAVEMENT TREATMENT
  - STRUCTURAL FILL > 200mm DEEP
  - EX. STRUCTURAL FILL > 200mm DEEP
  - DIRECTION OF FALL
  - OVERLAND FLOW
  - ALLOTMENT TO BE GRADED EVENLY IN DIRECTION OF FALL TO LEVELS INDICATED
  - CONCRETE EDGE STRIP WITH SUBSOIL DRAIN, "NO ROAD" SIGN & BARRIER
  - LIMIT OF WORKS
  - EXISTING TREE TO BE REMOVED
  - PERMANENT SURVEY MARK
  - TEMPORARY BENCH MARK
  - PROPOSED DRIVEWAY

**ROAD LAYOUT TABLE**

ROAD NAME	ROAD CLASSIFICATION	RESERVE WIDTH (m)	ROAD WIDTH (m)				KERB TYPE		VERGE WIDTH (m)	
			LIP to LIP	INV to INV	BACK to BACK	NTH/WEST	STH/EAST	NTH/WEST	STH/EAST	
MARTHA STREET	ACCESS STREET 2	16.00	6.40	7.00	7.30	B2	B2	4.35	4.35	
IRIS LOOP	ACCESS STREET 2	16.00	6.40	7.00	7.30	B2	B2	4.35	4.35	
POWER STREET (WEST)	ACCESS STREET 1	13.50	4.90	5.50	5.80	B2	B2	1.55	6.15	
POWER STREET (EAST)	ACCESS STREET 2	16.00	6.40	7.00	7.30	B2	B2	4.35	4.35	

**SERVICES OFFSET SCHEDULE**

ROAD NAME	GAS		RECYCLED WATER		WATER		ELECTRICITY		COMMUNICATIONS	
	SIDE	OFFSET (m)	SIDE	OFFSET (m)	SIDE	OFFSET (m)	SIDE	OFFSET (m)	SIDE	OFFSET (m)
MARTHA STREET	WEST	2.10	WEST	2.60	WEST	3.10	EAST	2.60	EAST	1.80
IRIS LOOP	NORTH	2.10	NORTH	2.60	NORTH	3.10	SOUTH	2.60	SOUTH	1.80
POWER STREET (WEST)	EAST	3.50	EAST	4.00	EAST	4.50	EAST	2.50	EAST	1.90
POWER STREET (EAST)	WEST	2.10	WEST	2.60	WEST	3.10	EAST	2.60	EAST	1.80



**WARNING**  
**BEWARE OF UNDERGROUND SERVICES**  
 The locations of underground services are approximate only and their exact position should be proven on site. No guarantee is given that all existing services are shown. Locate all underground services before commencement of works.  
**DIAL 1100 BEFORE YOU DIG**  
 www.1100.com.au

**RESERVE FENCING**  
 Where shown on drawings, white cypress post and rail fencing, harvested from sustainable forest (1.2m high), is to be constructed across the Council Reserve boundaries. Refer to Council Standard Drawing CCG709. A demountable section for vehicle access must be installed within the post and rail fencing to Council Standards. Refer to Council Standard Drawings CCG702 & CCG703.

**LOT FILLING**  
 Where shown on drawings, topsoil will be stripped from lots as part of the construction activity and replaced with fill to meet the finished surface levels. Where obstructions such as trees and rocks are removed fill will be placed back to meet the finished surface levels. Where the fill is greater than 200mm in depth structural fill complying to Section 4 AS3798-2007 will be used.

**CCTV INSPECTION OF DRAINAGE LINES - ALL DRAINAGE LINES INCLUDING CURVED PIPELINES ARE TO BE INSPECTED VIA REMOTE CAMERA PRIOR TO THE STATEMENT OF COMPLIANCE AT THE CONTRACTOR'S EXPENSE AND UNDER THE SUPERVISION OF COGG SUBDIVISIONS ENGINEER OR REPRESENTATIVE**


**NOTE:-**  
 CO-ORDINATES PROVIDED FOR PITS LOCATED IN FUTURE ROAD RESERVES ARE TO CENTRE OF PIT. CONTRACTOR IS TO ENSURE CORRECT ORIENTATION AND LOCATION IN ACCORDANCE WITH COGG STANDARDS TO FUTURE KERB & CHANNEL.

REVISION	ISSUED TO CLIENT FOR COMMENT	DATE	DES/DFT	APPD
A	ISSUED TO CLIENT FOR COMMENT	24.3.17	BB/BB	CB

**Warralily**  
 ARMSTRONG CREEK

Principal  
 Armstrong Creek Development Corporation  
 C/o Smec Australia Pty Ltd  
 Level 1, 47 Pakington Street, Geelong West

Designed  
 B.Barber  
 Drawn  
 B.Barber  
 Checked  
 C.Birkett  
 Authorised  
 S.McGlynn  
 Date  
 January 2017



© SMEC Australia Pty Ltd  
 ABN 47 065 475 149

These designs and drawings are the copyright of SMEC Australia Pty Ltd.  
 The drawing shall not be reproduced or copied, in whole or part, without the written permission of SMEC Australia Pty Ltd.  
 The contents of this drawing are electronically generated, are confidential and may only be used for the purpose for which they are intended.

**SMEC**  
 Member of the Surbana Jurong Group

**URBAN DEVELOPMENT**  
 Level 1, 47 Pakington Street, Geelong West VIC 3218  
 p +61 3 5228 3100 | f +61 3 5228 3199 | www.smecon.com

**Warralily**  
 Stage 72  
 City of Greater Geelong  
 Roadworks and Drainage  
 Layout Plan

Drawing No. 0595E-72-03 Rev A  
 Sheet No. 3 of 20

**Subject to Approval**  
 Not to be used for construction